BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2013-14/RD/WORK_INDENT9463/CALL-2

APPROVED SCHEDULE - B

Tender Notification No: No.EE/BTP/BBMP/E-PMT/16/2013-14, Date: 06.12.2013

Construction of Ward Office in Ward No. 10 (Doddabommasandra), Vidyaranyapura Sub Division. (Phase - 3).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K V SUBBA REDDY	
				In Figures	In Words
1	24	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work.	Cum	4419.84	Rupees Four Thousand Four Hundred Nineteen and Eighty Four Paise Only
2	19.2	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work.	Cum	5483.36	Rupees Five Thousand Four Hundred Eighty Three and Thirty Six Paise Only
3	152.88	Providing and fixing Special make glazed Vitrified tiles (Granomite finish) of approved make, quality and colour of sized 6000x600x10mm thick fixed on existing flooring wit ha special roffe adhesive for flooring and skirting etc., complete including providing spears at required interval and removing stains etc complete as per specifications and directions of engineer in charge of the work.	Sqm	1528.53	Rupees One Thousand Five Hundred Twenty Eight and Fifty Three Paise Only
4	152.88	For First Floor	Sqm	1530.2	Rupees One Thousand Five Hundred Thirty and Twenty Paise Only
5	87.26	Flooring with 25mm to 40mm thick polished tandur blue stone slabs using mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	1067.97	Rupees One Thousand Sixty Seven and Ninety Seven Paise Only
6	87.26	For First Floor	Sqm	1069.64	Rupees One Thousand Sixty Nine and Sixty Four Paise Only

7	1455.3	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S.square rods, or combination of M.S. flats and square rods as per approved design, drawning including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery etc complete as per specifications and directions of engineer in charge of the work.	Kgs	100.12	Rupees One Hundred and Twelve Paise Only
8	1245.51	For First Floor	Kgs	100.12	Rupees One Hundred and Twelve Paise Only
9	42.55	Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work.	Cum	6076.31	Rupees Six Thousand Seventy Six and Thirty One Paise Only
10	203.5	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	196.91	Rupees One Hundred Ninety Six and Ninety One Paise Only

K.V Jagadeesha Reddy

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92